

# Eliminate Construction Initiated Slides

Slides initiated during road construction are very serious and can have considerable human, environmental and operational costs.



1. Watch for key site indicators such as unstable soils, seepage, wet site vegetation, organic soils, and smooth bedrock.
2. Ensure drainage control is appropriate for the circumstances.
3. As an equipment operator, know your location and follow the plan.
4. Take extra caution through transition zones.
5. STOP work if things don't look right, and seek advice.